Mr. William F. Caton December 30, 1993 Page 2

Should there be any questions concerning this matter, please contact the undersigned. $\slash\hspace{-0.4cm}/\hspace{-0.4cm}/\hspace{-0.4cm}$

DDO/vm Enclosure

9797-000

pevorac	bу	OMB
3060-0	002	7
	120	1/05

FOR COMMISSION USE ONLY

FCC 301

COMMUNICATIONS COMMISSION WASHINGTON, B.C. 20044	F	·	*
ERMIT	FOR FCC USE		

APPLICATION FOR CONSTRUCTION PERMIT

FOR COMMERCIAL BROADCAST STATION

FLE NO. BPH-931230IB					
ection I - GENERAL INFORMATION					
1. APPLICANT NAME				ORI	GINAL
Wayne E. Tate				QIVI	OMAL
MAILING ADDRESS (Line 1) (Maximum 35 char	acters)			·	
310 E. De Young Street					
MAILING ADDRESS (Line 2) (if required) (Max	dimum 35 ch	naracters)		<u> </u>	
CITY		STATE OR C	OUNTRY (If fore	ign address)	ZIP CODE
Myrion	}	Illino	is	DEAT	62959
TE.L. HONE NUMBER (include area code)		CALL LETT	ERS OTHE	R FOC. IDENT	FIR (IF APPLICABLE)
(618) 993-2148		WVZA			
FOR MAILING THIS APPLICATION, SEE INSTRUC	TIONS FOR	SECTION 1	- GENERAL INF	ORMATION 6	1994
2. A. is a fee submitted with this application?			EA	A i i i .	Yes No
B. If No. indicate reason for fee exemption	(see 47 C.F.	R. Section 1	را :: 1112) and go to 9	LAAIV	IINERS
	_		50 10 1	,	
Governmental Entity	Noncom	mercial edu	cational license	е	
C. If Yes, provide the following information	n:				
Enter in Column (A) the correct Fee Type Code f		ce vou are a	polying for Fee	Type Codes m	av be found in the
"Mass Media Services Fee Filing Guide." Column (E		-			•
the result obtained from multiplying the value of t	the Fee Type	Code in Co	olumn (A) by the	number listed	in Column (B).
(A)(B)			(C)		
FEE MULTIP			JE FOR FEE TYPE IN COLUMN (A)	E	OR FCC USE ONLY
(i reduse	-		HT COLDIVIT (A)		
1 P R 0 0 0	1	\$ 56	5.00		
o be used only when you are requesting concurre	ent actions v	which result	in a requirement	to list more th	an one Fee Type Code
(A) (B)	7 7		(C)		OR FCC USE ONLY
(2) 0 0 0	1	\$			3
400 444 4440470 010444 1440	20 (4)	TOTAL	AMOUNT REMITTE		
ADD ALL AMOUNTS SHOWN IN COLUMN C, LINE THROUGH (2), AND ENTER THE TOTAL HERE.	5 (1)		THIS APPLICATION		OR FCC USE ONLY
THIS AMOUNT SHOULD EQUAL YOUR ENCLOSED REMITTANCE.		\$ 56	5 - 00		565 DO
				<u>نا ل</u>	
3. This application is for (check one box)	MA	[X FM	TV	
(b) Channel No. or Frequency	(b) Princip	pal	C1	ty	State
224B1 92.7	Commi	*	Herrin		, IL
[4.]	L	1			

Section 1 - GENERAL INFORMATION (Page 2)

1

(c) Ch	neck one of the	ne following boxe	E		
	Application	for NEW station			
	MAJOR chan	nge in licensed fac	cilities call sign:		
X	MINOR chan	nge in licensed fac	cilities, call sign:	WVZA	
	MAJOR modi	ification of constr	uction permit; call sign:		
	File No. of ∝	onstruction permit			
	MINOR modi	fication of constr	uction permit; call sign:		
	File No. of co	onstruction permit			
	AMENDMENT	to pending applica	ation; Application file number:		
		•	form to amend a previously filed application. Should reportions of the form that contain the amended inform	*	ever, please
4. Is t	his application	n mutually exclusi	ve with a renewal application?	үе	es No
Ιſ	Yes, state:	Call letters	Community of License		
••	· mi oraro		City	State	

SECTION VI - EQUAL EMPLOYMEN. C	PPORTUNITY PROGRAM	
h Does the applicant propose to emplo	y five or more full-time employees?	Yes No
If Yes, the applicant must include Opportunity Program Report (FCC	an EEO program called for in the separate Broadcast Equal Empio 398-A).	yment
SECTION VII - CERTFICATIONS		
1. Has or will the applicant comply wi	ith the public notice requirement of 47 C.F.R. Section 73.3580?	X Yes No
	nce, in good faith, that the site or structure proposed in Section s transmitting antenna, will be available to the applicant for	X Yes No
If No, attach as an Exhibit, a full ex	plantion.	Exhibit No.
LID	i on applicant's ownership of the proposed site or structure, ned such reasonable assurance by contacting the owner or structure.	
Name of Person Contacted	Dennis Doelitzsch	
Telephone No. (include area code)	(618) 997-8123	
Person contacted: Icheck one box be	[ee]	
X Owner Ow	oner's Agent Other (specify)	
not subject to a denial of federal of the Anti-Drug Abuse Act of it applicant (e.g., corporation, partner application is subject to a denial of	tifies that, in the case of an individual applicant, he or she is benefits that includes FCC benefits pursuant to Section 5301 938, 21 U.S.C. Section 882, or, in the case of a non-individual ership or other unincorporated association), no party to the f federal benefits that includes FCC benefits pursuant to that rty" for these purposes, see 47 C.F.R. Section 12002(b).	X Yes No
of the United States because of the	y claim to the use of any particular frequency as against the reprevious use of the same, whether by license or otherwise, application. (See Section 304 of the Communications Act of 1934, as an	and requests an
The APPLICANT acknowledges that	all the statements made in this application and attached exhibit	s are considered

The APPLICANT acknowledges that all the statements made in this application and attached exhibits are considered material representations, and that all exhibits are a material part hereof and incorporated herein.

The APPLICANT represents that this application is not filed for the purpose of impeding, obstructing, or delaying determination on any other application with which it may be in conflict.

In accordance with 47 C.F.R. Section 186, the APPLICANT has a continuing obligation to advise the Commission, through amendments, of any substantial and significant changes in information furnished.

968 2

WILLFUL FALSE STATEMENTS MADE ON THIS FORM ARE PUNISHABLE BY FINE AND/OR IMPRISONMENT
U.S. CODE, TITLE 18, SECTION 1001), AND/OR REVOCATION OF ANY STATION LICENSE OR CONSTRUCTION PERMIT
(U.S. CODE, TITLE 47, SECTION 312(MI)), AND/OR FORFEITURE (U.S. CODE, TITLE 47, SECTION 503).

I certify that the statements in this application are true and correct to the best of my knowledge and belief, and are made in good faith.

Name of Applicant	Signature
Wayne E. Tate	
Date	Title
December 29, 1993	Permittee

FCC NOTICE TO INDIVIDUALS REQUIRED BY THE PRIVACY ACT AND THE PAPERWORK REDUCTION ACT

illing of personal information requested in this application is authorized by the Communications Act of 1934, as amended. The Commission will use the information provided in this form to determine whether grant of the application is in the public interest in reaching that determination, or for law enforcement purposes, it may become necessary to refer personal information contained in this form to another government agency. In addition, all information provided in this form will be available for public inspection. If information requested on the form is not provided, processing of the application may be delayed or the application may be returned without action pursuant to the Commission's rules. Your response is required to obtain the requested authority.

Public reporting burden for this collection of information is estimated to vary from 72 hours 40 minutes to 347 hours 25 minutes with an average of 218 hours 32 minutes per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing the burden, can be sent to the Federal Communications Commission, information Resources Branch, Room 416, Paperwork Reduction Project Washington, D.C. 20564, and to the Office of Management and Budget, Paperwork Reduction Project (3080-0027), Washington, D.C. 20503.

THE FOREGOING NOTICE IS REQUIRED BY THE PRIVACY ACT OF 1974, P.L. 93-579, DECEMBER 31, 1974, 5 U.S.C. 562». , AND THE PAPERWORK REDUCTION ACT OF 1980, P.L. 96-511, DECEMBER 11, 1980, 44 U.S.C. 3607.

ENGINEERING EXHIBIT

APPLICATION FOR CONSTRUCTION PERMIT TO UPGRADE TO CLASS B1 AND INCREASE POWER

WAYNE E. TATE WVZA(FM), HERRIN, ILLINOIS

DECEMBER 1993

COPYRIGHT © 1993 BY EVANS ASSOCIATES

ALL RIGHTS RESERVED

ENGINEERING STATEMENT

This Engineering Statement and the attached figures have been prepared by B. Benjamin Evans of Evans Associates, Consulting Communications Engineers in Thiensville, Wisconsin, on behalf of Wayne E. Tate, permittee of Radio Station WVZA(FM) in Herrin, Illinois.

PRELIMINARY

WVZA is presently authorized to operate on Channel 224A (92.7 MHz) with 3.3 kilowatts effective radiated power and 132 meters antenna height above average terrain, from a transmitter site which is the existing site of the WDDD(AM), Johnston City, IL daytime antenna, and WDDD-FM, licensed to Marion, IL. By this application, WVZA proposes to upgrade to Class B1 status on Channel 224, in accordance with the Commission's new "one-step" procedure, and to increase the transmitting facilities using the authorized site. The assignment of Channel 224B1 to Herrin will require that station KYLS in Ironton, MO move off its present Channel 224A. An application is being filed simultaneously with the instant application to change KYLS to Channel 225A, as per the Commission's "one-step" procedure.

The facilities requested herein are being applied for under Section 73.215 of the FCC Rules in order to permit short-spacings to WBKR, Channel 223C in Owensboro, KY, and WSEI, Channel 225B in Olney, IL. A waiver of Section 73.215 is hereby requested in order to permit a contour overlap with station WBKR.

AVAILABILITY OF FULLY-SPACED SITE

As required under the "one-step" procedure for upgrades, a fully-spaced site exists for Channel 224B1 at Herrin, under the condition that KYLS change to Channel 225A as mentioned above (see attached Figure 5-A). The coordinates of this site are:

N. Lat. 37°-45'-51"; W. Long. 89°-13'-42"

From the above site, it is 18.3 kilometers to Herrin on a bearing of 76° True. Since a full Class B1 station's predicted 70 dBu contour extends an average of 23.2 kilometers, city of license coverage from this site is assured.

Engineering Statement - Page 2 WVZA(FM), Herrin, IL

PROPOSED FACILITIES

A directional antenna is being proposed herein, which is described fully in attached Figure 3. It is proposed herein to increase the effective radiated power to 14.5 KW in the direction of maximum radiation. The antenna HAAT is being revised slightly, from 132 meters to 133 meters. The power and antenna height combination proposed is equivalent to 25 KW ERP and 100 meters HAAT, the maximum for a Class B1 station.

The proposed WVZA facility will serve an area of 3,776 square kilometers and a population of 171,226 persons with a predicted 1 mv/m signal or better. The area was determined by numerical integration. The population was determined on the basis of the 1990 U.S. Census figures.

AUTHORITY REQUESTED UNDER SECTION 73.215

The instant proposal would short-space WBKR, Owensboro, KY by 26 kilometers. The maximum amount of short-spacing according to Section 73.215 is 28 kilometers; thus, the proposal is in compliance with the minimum spacing for a short-spaced site.

The directional antenna showed herein was designed specifically so that WVZA would maintain the same signal as is presently authorized in the direction of WBKR over a 110-degree arc. As seen in attached Figure 4, however, WVZA would receive contour overlap within its protected Class B1 contour. This overlap is due entirely to the fact that the protected contour of WVZA becomes 57 dBu instead of 60 dBu. The Class B1 facilities proposed herein would not exceed the authorized Class A facilities of WVZA, which causes no overlap with WBKR, in the direction of WBKR. Therefore, the "creation" of overlap as a result of this proposal is due entirely to the different contour level used for Class B1 than for Class A, when, in fact, no overlap will be created beyond where it had existed previously. Figure 4 shows this to be the case. The proposed 57 dBu does not extend past the 57 dBu contour of the present Class A facility where there is existing overlap.

A waiver, therefore, is requested to permit this contour overlap condition. Grant of this waiver is in the public interest because:

1) WVZA would then be able to use its presently authorized site, which is a multi-station site, rather than bear the burden of building a new tower at a different site just for the new WVZA facility;

Engineering Statement - Page 3 WVZA(FM), Herrin, IL

- 2) as shown above, the signal toward WBKR would not be increased beyond WVZA's present authorization, and in addition, WBKR would not receive overlap within its protected contour;
- 3) with the waiver, WVZA would not be required to reduce power to the east, and thus could retain all of its presently authorized coverage;
- 4) with the waiver, WVZA would not be required to employ a directional antenna with a maximum-to-minimum radiation ratio in excess of 15 dB in order to be at full Class B1 power in the major lobe of the pattern, thereby greatly reducing the possibility of "picket-fencing" in areas to the east.

The facility proposed herein would short-space WSEI, Olney, IL by 16 kilometers, which is less than the maximum amount that WSEI can be short-spaced (31 kilometers). As seen in Figure 4, all contour protection criteria regarding WSEI are observed.

BLANKETING

The proposed blanket contour, calculated in accordance with Paragraph 73.318(a) of the Commission's rules, extends a maximum of 1.5 kilometers from the transmitter site. The applicant will resolve all known complaints of blanketing interference within this contour in accordance with Section 73.318.

COVERAGE REQUIREMENTS

The herein-proposed facility will cover all of the city of Herrin with a 3.16 mv/m signal or better.

INTERFERENCE CONSIDERATIONS

As mentioned previously, WVZA shares its transmitter site with WDDD(AM) and WDDD-FM. If instances of objectionable interference to WDDD(AM), WDDD-FM, or any other station due to the proposed facility should arise, the applicant will cooperate fully, as appropriate, to eliminate the interference.

Engineering Statement - Page 4 WVZA(FM), Herrin, IL

The signals of WVZA are not expected to mix with WDDD-FM to cause receiver-induced third order intermodulation (RITOI) interference to another station. If, however, interference of this type does occur, WVZA will satisfy all verified complaints of reception problems, except those involving mobile or battery-powered receivers.


ENVIRONMENTAL CONSIDERATIONS

Because of the fact that this proposal involves installing an antenna on an existing antenna structure without increasing the structure height, this proposal will have no physical environmental impact.

The proposed facility meets the radio frequency radiation exposure guidelines recommended in ANSI C95.1-1982. Using calculation methods described in OST Bulletin 65, the total power density due to WDDD(AM), WDDD-FM and the proposed WVZA facility, would be less than the maximum permissible level in areas around the tower that are accessible by casual approach. The power density due to WDDD-FM and WVZA, added together, at any location two meters above ground beneath the antennas, would not exceed 0.244 mW/cm², or 24.4% of the ANSI maximum. The applicant will install a fence around the tower with a radius of 2 meters, if the existing fence does not meet this specification. Using Table 1 of Appendix D of the Bulletin, the power density at 2 meters due to WDDD(AM), which operates with 250 watts, would be 62.5% or less of the ANSI maximum. The total power density due to all three stations, then, would be 86.9% or less of the ANSI maximum. Therefore, the proposed facility is within the ANSI guidelines for exposure to the public.

When construction or maintenance is to be performed at the site, workers will be protected from overexposure to RF radiation by either reducing transmitting power or turning off the power completely, as necessary. Prior to commencement of program tests, an agreement among the users of the tower will be in effect requiring the stations to do what is necessary to assure worker safety with respect to RF exposure.

Therefore, in view of the above, this proposal is not deemed to be a major environmental action.



Engineering Statement - Page 5 WVZA(FM), Herrin, IL

ATTACHMENTS

Affidavit

FCC Form 301, Section V-B

Figure 1 ---- Vertical Plan Sketch of Antenna Structure

Figure 2 - - - - Map Showing Proposed Predicted Service Contours

Figure 3 ---- Directional Antenna Patterns & Description

Figure 4 ---- Contour Study Per Section 73.215 of FCC Rules

Figure 5-A - - - Allocation Study - Channel 224B1 Reference Point

Figure 5-B - - - Allocation Study - Present WVZA Site

.cvans\document\ben\wvza_es.doc

AFFIDAVIT

COUNTY OF OZAUKEE	}	SS
STATE OF WISCONSIN		

B. BENJAMIN EVANS, being duly sworn upon oath deposes and says:

That his qualifications are a matter of record with the Federal Communications Commission:

That he is a Consulting TeleCommunications Engineer in Wisconsin, and is a partner in the firm of Evans Associates;

That this firm has been retained by Wayne E. Tate to prepare this engineering exhibit;

That he has either prepared or directly supervised the preparation of all technical information contained in this engineering statement, and that the facts stated in this engineering statement are true of his knowledge, except as to such statements as are herein stated to be on information and belief and as to such statements he believes them to be true.

Subscribed and sworn to before me this 9th day of December, 1993.

atricia Celagner My Commission expires 5/15/94.

			FOF	COMMIS	SION USE ONLY		
			File	No.			
Section V-B - FM BROADCAST ENGIN		T ENGINEERING DATA	ASI	B Referral	Date		
			Ref	erred by			
Name of Appli	cant						
	Wayne E. Ta	ate					
Call letters (if	issuedl	is this application window?	on being fil	ed in resp	oonse to a	Yes	X No
WVZA		If Yes, specify	closing date:				
Purpose of Ap	plication: Ichack appropria	te box(es)					
Constr	uct a new (main) facilit	у [Construc	t a new a	auxiliary facilit	у	
X Modify	y existing construction	permit for main	Modify facility	existing c	construction per	mit for aux	iliary
Modify	y licensed main facility	[Modify	licensed a	uxillary facility	у	
If purpose is to affected.	o modify, indicate below	v the nature of change(s)	and specify	the file	number(s) of the	ne authoriza	ions
Anten:	na supporting-structure	helght	X Effectiv	e radiated	i power		
Anten	na height above averag	e terrain	Frequen	су			
Anten	na location	_ [X Class				
Main S	Studio location	[vmarize bi	rieflyl ectional ante	enna	
201 27 1	() pimt 020004T	.	Dpcc11;	, a dire	octional and	ania	
File Numbe	r(s) <u>BMPH-9308041</u>	8					
1. Allocation:							
Channel No.	Princ	cipal community to be se	rved:		Class Icheck	only one box	belos?
	City	County		State		B1	в 🔲 с:
224	Herrin	Williamson		IL	C2] C1	C
	on of antenna. dress, city, county and s No change	tate. If no address, specif	y distance a	nd bearin	g relative to th	e nearest to	wn or
of array. O		est second). If mounted or location. Specify South I will be presumed.					
Latitude	37 ° 45	15 L	ongitude	88	56	05	5 "
3. Is the suppor		e as that of another static	on(s) or prop	osed in a	nother pending	X Yes	No
If Yes, give	call letter(s) or file nu	mber(s) or both.	WDDD-FM,	WDDD (AN	1)		
If proposal	involves a change in h	eight of an existing struc	cture, specif	y existing	height above	ground leve	l includin
	l other appurtenances, a		-				
			N/A				

4. Does the application propose to c if Yes, list old coordinates.	correct previous site coor	dinates?		Ye	es X No
Latitude	1 N	Longitude	0	,	"
5. Has the FAA been notified of the If Yes, give date and office who determination, if available.		N/A attach as an Exhibit a co	py of FAA	Ye	es No
Date	Office where filed				
6. List all landing areas within 8 k nearest runway.	km of antenna site. Speci	fy distance and bearing	from structur	e to nearest	point of the
Landing Area	Di	stance (km)	Bearin	ng (degrees I	(rue)
(a)	<u>N</u>	I/A			
(b)					
7. (a vation: Its the nearest seter)	,				
(1) of site above mean sea lev	vel;		_	147	meters
(2) of the top of supporting s appurtenances, and lighting	. -	including antenna, all ot	her	149	meters
(3) of the top of supporting s	structure above mean sea	a level [(aX1) + (aX2)]	_	296	meters
(b) Height of radiation center: (t	o the nearest meter? H =	Horizontal; V - Vertical			
(1) above ground				123	meters (H)
			_	123	meters (V)
(2) above mean sea level [(aX1) + (bX1)]		***************************************	270	meters (H)
				270	meters (V)
(3) above average terrain				133	meters (H)
			_	133	meters (V)
8. Attach as an Exhibit sketch(es) o in Question 7 above, except item specify heights and orientations	n 7(b)(3). If mounted on a	n AM directional-array	element	Exhib Fig.	oit No.
9. Effective Radiated Power: (a) ERP in the horizontal plane	14 5	kw (H*) 14.5	kw (V*)		
(b) Is beam tilt proposed?		Kw (III)	~~ (V -)	Ye	es X No
If Yes, specify maximum ERF vertical elevational plot of r				Exhib	bit No.
Polarization		kw (H+)	KW (V)		

4. Does the appli	cation propose to corred coordinates.	ect previous site coor	dinates?		Y	es X No
Latitude	0	1	Longitude	0	,	*
If Yes, give d	peen notified of the pritate and office where n, if available.		/	olt a copy of FAA		es No
Date		Office where filed				
6. List all landing nearest runw	ng areas within 8 km -	of antenna site. Spec	ify distance and be	earing from struc	ture to nearest	point of th
	Landing Area	Di	istance (km)	Bea	ring (degrees	True)
(a)		1	N/A			
(b)		_				
7. (s. vation:	ito the nearest meter)					
(1) of site	above mean sea level;				147	meters
	top of supporting struences, and lighting,	-	(including antenna	, all other	149	meters
(3) of the	top of supporting struc	cture above mean se	a level [(a)(1) + (a)	(2)]	296	meters
(b) Height of r	radiation center: (to the	ne nearest meterl H =	Horizontal; V • Ver	tical		
(1) above (ground				123	meters (H)
					123	meters (V)
(2) above	mean sea level [(a)(1) + (bX1)]			270	meters (H)
					270	meters (V)
(3) above	average terrain				133	meters (H)
					133	meters (V)
in Question 7	Exhibit sketch(es) of the same of the sketch	b)(3). If mounted on a	an AM directional-a	rray element,	Exhi Fig.	bit No.
9. Effective Rad	lated Power:					
(a) ERP in the	e horizontal plane	14.5	kw(H*)1	.4.5 kw(V*)		
(b) Is beam ti	lt proposed?			-	Y	es X No
	ecify maximum ERP in levational plot of radia		ed beam, and attack	h as an Exhibit a	,	blt No.
Polarizati	.on		KW (N-)	KW (V)		

SECTION V-B - FM BROADCAST ENGINEERING DATA (Page 3)

10. is a directional antenna proposed?	X Yes No
If Yes, attach as an Exhibit a statement with all data specified in 47 C.F.R. Section 73.316, including plot(s) and tabulations of the relative field.	Exhibit No. Fig. 3
11. Will the proposed facility satisfy the requirements of 47 C.F.R. Sections 73.315(a) and (b)?	X Yes No
If No, attach as an Exhibit a request for waiver and justification therefor, including amounts and percentages of population and area that will not receive 3.16 mV/m service.	Exhibit No.
12. Will the main studio be within the protected 3.16 mV/m field strength contour of this proposal?	X Yes No
If No, attach as an Exhibit justification pursuant to 47 C.F.R. Section 73.1125.	Exhibit No.
13. (a) Does the proposed facility satisfy the requirements of 47 C.F.R. Section 73.207?	Yes X No
(b) If the answer to (a) is No. does 47 C.F.R. Section 73.213 apply?	Yes X No
(c) If the answer to (b) is Yes, attach as an Exhibit a Justification, including a summary of previous waivers.	Exhibit No.
 (d) If the answer to (a) is No and the answer to (b) is No, attach as an Exhibit a statement describing the short spacing(s) and how it or they arose. Application is made pursuant to Section 73.215 of FCC Rules (e) If authorization pursuant to 47 C.F.R. Section 73.215 is requested, attach as an Exhibit a complete engineering study to establish the lack of prohibited overlap of contours involving affected stations. The engineering study must include the following: 	Exhibit No. Eng. Exhibit No. Fig. 4
 (i) Protected and interfering contours, in all directions (360), for the proposed operation. (2) Protected and interfering contours, over pertinent arcs, of all short-spaced assignments, applications and allotments, including a plot showing each transmitter location, with identifying call letters or file numbers, and indication of whether facility is operating or proposed. For vacant allotments, use the reference coordinates as the transmitter location. (3) When necessary to show more detail, an additional allocation study utilizing a map with a larger scale to clearly show prohibited overlap will not occur. (4) A scale of kilometers and properly labeled longitude and latitude lines, shown across the entire exhibit(s). Sufficient lines should be shown so that the location of the sites may be verified. 	
(5) The official title(s) of the map(s) used in the exhibits(s).	
14. Are there: (a) within 60 meters of the proposed antenna any proposed or authorized FM or TV transmitters, or any nonbroadcast lexcept citizens bend or emeteur! radio stations, or (b) within the blanketing contour, any established commercial or government receiving stations, cable head-end facilities, or populated areas, or (c) within ten (10) kilometers of the proposed antenna, any proposed or authorized FM or TV transmitters which may produce receiver-induced intermodulation interference?	X Yes No
If Yes, attach as an Exhibit a description of any expected, undesired effects of operations and remedial steps to be pursued if necessary, and a statement accepting full responsibility for the elimination of any objectionable interference (including that caused by receiver-induced for other types of modulation) to facilities in existence or authorized or to radio receivers in use	Exhibit No. Eng.

prior to grant of this application. (See 47 C.F.R. Sections 73.315(b), 73.316(e) and 73.318.)

SECTION V-B - FM BROADCAST ENGINEERING DATA (Page 4)

15.	Attach as an Exhibit a 75 minute series U.S. Geological Survey topographic quadrangle map that shows clearly, legibly, and accurately, the location of the proposed transmitting antenna. This map must comply with the requirements set forth in Instruction V (D). The map must further clearly and legibly display the original printed contour lines and data as well as latitude and longitude markings, and must bear a scale of distance in kilometers.	Exhibit No. On File No Change
16.	Attach as an Exhibit Inser the source! a map which shows clearly, legibly, and accurately, and with the original printed latitude and longitude markings and a scale of distance in kilometers.	Exhibit No. Fig. 2
	(a) the proposed transmitter location, and the radials along which profile graphs have been prepared;	
	(b) the 3.16 mV/m and 1 mV/m predicted contours; and	
	(c) the legal boundaries of the principal community to be served.	
17.	Specify area in square kilometers (1 sq. mi 259 sq. km) and population (latest census) within the predicted 1 mV/m contour.	
	Area 3,776 sq. km. Population 171,226 (1990 Census)	
18.	For an application involving an auxiliary facility only, attach as an Exhibit a map (Sectional Aeronautical thant or equivalent) that shows clearly, legibly, and accurately, and with latitude and longitude markings and a scale of distance in kilometers:	Exhibit No. N/A
	(a) the proposed auxiliary 1 mV/m contour; and	
	(b) the 1 mV/m contour of the licensed main facility for which the applied-for facility will be auxiliary. Also specify the file number of the license.	
19.	ain and coverage data Ite be calculated in accordance with 47 C.F.R. Section 73.3131	
	Source of terrain data: Icheck only one box below?	
	X Linearly interpolated 30-second database 75 minute topographic map	
	(Source: National Geophysical Data Center)	
	Other Ibriefly summarize	

	Height of radiation center above average elevation of radial from 3 to 16 km (meters) ERP(KW)		Predicted Distances			
Radial bearing (degrees True)			To the 3.16 mV/m contour (kilometers)	To the 1 mV/m contour (kilometers)		
304 *	144.5	14.5	24.16	40.66		
o	143.2	10.5	22.24	37.81		
45	123.7	3.2	15.40	27.16		
90	122.5	3.2	15.32	27.03		
135	128.1	3.2	15.68	27.60		
180	126.6	8.2	19.68	33.83		
225	138.2	14.5	23.66	39.88		
270	132.6	14.5	23.19	39.16		
315	149.4	14.5	24.54	41.25		

^{*}Radial through principal community, if not one of the major radials. This radial should NOT be included in the calculation of HAAT.


20. Environmental Statement/See 47 C.F.R. Section 1.1301 et seq.1

Would a Commission grant of this application come within Section 1.1307 of the FCC Rules, such that it may have a significant environmental impact?	Yes X No
If you answer Yes, submit as an Exhibit an Environmental Assessment required by Section 1.1311.	Exhibit No.
If No, explain briefly why not See Engineering Statement	

CERTIFICATION


I certify that I have prepared this Section of this application on behalf of the applicant, and that after such preparation, I have examined the foregoing and found it to be accurate and true to the best of my knowledge and belief.

Name (Typed or Printed)	Relationship to Applicantie.g., Consulting Engineer
B. Benjamin Evans	Consulting Engineer
Signature	Address (Include ZIP Code)
A. Bujan han	216 N. Green Bay Road Thiensville, WI 53092
Date	Telephone No. Include Area Codel
December 9, 1993	(414) 242-6000




VERTICAL PLAN SKETCH OF ANTENNA STRUCTURE

WVZA (FM)
Herrin, Illinois
Channel 224 B1 14.5 kW ERP 133m HAAT



HORIZONTAL PLANE RELATIVE FIELD PATTERN



FREQUENCY: 92.7 MHz ANTENNA TYPE:

RMS: 0.790 MAJOR LOBE GAIN: 2.4 ELEVATION GAIN: 1.5

COMMENTS:



TABULATION OF HORIZONTAL PLANE RADIATIONS


Radio Station WVZA(FM) Herrin, Illinois

Azimuth (deg T)	Relative Field	Power (KW)	Power (dBk)	Azimuth (deg T)	Relative Field	Power (KW)	Power (dBk)
				the same than the same than			
0.0	0.850	10.476	+10.20	190.0	0.850	10.476	+10.20
10.0	0.750	8.156	+9.11	200.0	0.950	13.086	+11.17
20.0	0.625	5.664	+7.53	210.0	1.000	14.500	+11.61
30.0	0.525	3.997	+6.02	220.0	1.000	14.500	+11.61
40.0	0.473	3.244	+5.11	225.0	1.000	14.500	+11.61
45.0	0.473	3.244	+5.11	230.0	1.000	14.500	+11.61
50.0	0.473	3.244	+5.11	240.0	1.000	14.500	+11.61
60.0	0.473	3.244	+5.11	250.0	1.000	14.500	+11.61
70.0	0.473	3.244	+5.11	260.0	1.000	14.500	+11.61
80.0	0.473	3.244	+5.11	270.0	1.000	14.500	+11.61
90.0	0.473	3.244	+5.11	280.0	1.000	14.500	+11.61
100.0	0.473	3.244	+5.11	290.0	1.000	14.500	+11.61
110.0	0.473	3.244	+5.11	300.0	1.000	14.500	+11.61
120.0	0.473	3.244	+5.11	304.0	1.000	14.500	+11.61
130.0	0.473	3.244	+5.11	310.0	1.000	14.500	+11.61
135.0	0.473	3.244	+5.11	315.0	1.000	14.500	+11.61
140.0	0.473	3.244	+5.11	320.0	1.000	14.500	+11.61
150.0	0.473	3.244	+5.11	330.0	1.000	14.500	+11.61
160.0	0.525	3.997	+6.02	340.0	1.000	14.500	+11.61
170.0	0.625	5.664	+7.53	350.0	0.950	13.086	+11.17
180.0	0.750	8.156	+9.11			,	

EVANG ASSUCIATES

Consulting Engineers

ELEVATION PATTERN



Custome	r:					date:		
Frequen	cy:	Type:	Ba	ys:	3	Spacing:	1.0	wave
Beam ti	lt: 0		Null fill:	0 8	<u>. </u>		<u>.</u>	
Notes:	Elevation	pattern	plotted in 1	<u>elat</u>	ive	field		




Figure 3-D

DESCRIPTION OF PROPOSED DIRECTIONAL ANTENNA

WVZA(FM), Herrin, Illinois

In order to achieve the directional antenna pattern shown in attached Figure 3-A, it is proposed to employ a custom 3-bay full-wavelength spaced directional antenna to be side-mounted on an existing tower.

Both horizontal and vertical polarizations will be utilized. Horizontal and/or vertical parasitic elements will be installed, as appropriate, so that the measured pattern in both the horizontal and vertical polarizations will match the pattern in Figure 3-A as closely as possible.

Neither the horizontal nor the vertical radiation component of the pattern in Figure 3-A changes more than 2 dB per 10 degrees of azimuth, nor does either component exceed a maximum-to-minimum radiation ratio of 15 dB.

The antenna will be mounted on the tower in accordance with specific instructions provided by the manufacturer. The antenna will not be mounted on the same tower level as any other antenna, nor will it be mounted within the minimum horizontal or vertical distance to any other antenna which is specified by the manufacturer as being necessary for proper operation.

